

2.8T PLANT TRAILER

Build Quality	Heavy duty
Galvanised	Yes (hot dipped)
Tie-Downs	6 tie-down lugs
Wheels	14" mag 5-stud (Ford) pattern
Tyres	New steel belted tubeless radial
Floor	2.5mm checker plate
Mud Guards	2.5mm checker plate
Axles	50mm solid square drop
Suspension	7 leaf springs with HDrocker / roller
Brakes	Electric drum w/ breakaway
Chassis	100x50mm HD box construction
Ramp Width	400 mm (gas-strut assisted)
Deck Size	3500 x 1880 mm
Tare Weight	740 kg
GVM Capacity	2,800 kg
Drawbar	1800mm, 100x50x4mm box construction
LED Lights	Yes (Australian Roads Compliant)
Plug Type	12 Pin Flat – (AR Compliant)
Compliance Plate	Yes
VIN	Yes
Spare Wheel	Yes
Jockey Stand	Yes – swing up model
Bucket Rests	Yes
Storage Area	Yes
Warranty	12 months

DMD PLANT HIRE

Danny Starkey
 0419 684 950
dan@dmdplanthire.com.au
www.dmdplanthire.com.au

79 Pearsons Road
 Lake McDonald
 QLD 4563

ABN 29 100 149 750